

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work : Construction of Yoga and Meditation Building near Hopcoms at Vidyaranyapura in Ward No. 09, Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	8.40	Earth work in surface excavation in Ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road, drains and trenches of pipes lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m excavated surface levelled and neatly dressed earth to be levelled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work.	Cum	124.02	
2	45.28	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods etc complete as per specifications and directions of engineer in charge of the work.	Cum	223.66	
3	4.88	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4211.38	
4	12.09	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6 , stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	3484.22	
5	6.21	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6 , edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4148.84	
6	45.28	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour etc complete as per specifications and directions of engineer in charge of the work.	Cum	99.64	
7	13.08	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	78.44	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
14	108.48	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	199.28	
15	164.14	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	19.08	
16	107.79	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	165.36	
17	48.87	Providing and laying flooring with M15 cement concrete, 40mm thick using broken granite metal of 20mm and down size laid to line and level in one layer and finish with a floating coat of neat cement, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	284.08	
18	44.21	Flooring with 25mm to 40mm thick polished Thandur blue stone slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1017.60	
19	41.61	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs , landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	284.08	
20	4.77	Providing and removing centering, shuttering, strutting, propping etc., for chajjas , corbels etc., including edges including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	242.74	
21	79.22	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	220.48	
22	4.41	Supply and fixing pressed steel door frames size 125x65 mm manufacture from 1.25mm thick carbon steel or imported steel strips with mitred joints of 900 for door openings and sutters made out of seasoned honne wood, styles of 30mm, thick with lock rail of 160mm, width, top and side rails of 100mm, width width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be not proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years, this shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting wit enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc, complete the hollow portion of the frame to be filled with cement concrete 1:2:4. etc complete as per specifications anand directions of engineer in charge of the wor	Sqm	3710.00	

ಕರಡು ಬೆಂಚರ್ ಪಡೆದೊಂದಕ್ಕೆ ತಿದ್ದುಪಡಿ ಮಾಡಿದಂತೆ/


ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.

ತಿದ್ದುಪಡಿಗೆ ಸಂಖ್ಯೆ N.J.L

Supervising Engineer. (A)
Yelahanka Zone
BBMP, Bangalore-92

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092


Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
23	4.59	"Supplying and fixing pressed steel window frame of size 100x50mm manufacture from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 90degree for window openings and shall be suitable to fix M.S grills as per design and drawings using 12mm dia rods at 100mm centre to centre horizontally and two members of M.S flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S flats with 16mm size lugs, and 8nos, of 100mm size hinger, 4nos	Sqm	4028.00	
24	164.14	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	59.36	
25	107.79	Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thoroughy brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work. with Primer	Cum	78.44	
26	1.00	Providing and fixing white vitreous china clay, flat back wash basin of size 630x450mm with pair of 15mm C.P brass pillar taps with C.I./M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets ,cutting and making good the wall and floor wherever required, including cost of materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Unit	3773.60	
27	30.00	Providing and fixing to wall, ceiling and floor, low density poluethylene pipes kgs/sq.cm working pressure 32mm outside diameter, compression type fittings, wall clips, making good the wall ceiling and floor cost of materials, labour charges HOM of equipments and testing exeluding cost of fittings, etc complete as per specifications and directions of engineer in charge of the work.	Rmtr	152.39	
28	1000	Supppying water storage tanks made of virgin polymer (LLDPE) with two layers outer black of blue and inner white layer of approved quality and make, conforming etc complete as per specifications and directions of engineer in charge of the work.	L	6.36	
29	4	Providing and fixing in position brass bib cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads etc complete as per specifications and directions of engineer in charge of the work.	Each	192.44	
30	2.25	Providing colour glazed tiles of size 10mm thick for flooring, treads of steps and landing, laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing using white cement with matching colour pigment, including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	882.98	
31	9.84	Providing skirting, dado, rises of steps with Colour glazed tiles 15x15cms 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	926.44	


 Executive Engineer
 Syahareyanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
32	35.00	Providing and fixing in wall surface 4 kg/sq.cm H.D.P.E. rain down water pipes 90 mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.	m	447.32	
33	1	Square Tank Cover "ISI" marked 24"x24x pf 100kg in weight Page No. XXXI) etc complete as per specifications and directions of engineer in charge of the work.	L/S	5009.00	
34	45.00	Groove Cutting : Supplying ... dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary 32 mm dia 2.5mm thick etc complete as per specifications and directions of engineer in charge of the work.	Mtrs	68.00	
35	2	Supplying and flush mounting teak wooden box with out front plank made of not less than 12mm thick wood after due groove cutting necessary masonry patch work 10"X7"X3" (300X228X76mm) etc complete as per specifications and directions of engineer in charge of the work.	Each	68.00	
36	2	8"X6"X3" (300X228X76mm)		52.00	
37	12	Supplying and fixing PVC/metal conduit accessories special type Junction Box 32 mm Junction Box etc complete as per specifications and directions of engineer in charge of the work.	Each	29.00	
38	4.00	Deep 32 mm Junction Box		33.00	
39	4.00	Fan Box 18 /SWG		57.00	
40	4	Point Wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using Copper PVC insulated multi strand 2x1.5 Sqmm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet gang box the other end of the wires shall be terminated with sufficient loose length in a wood PVC round block complete for each outlet KPWD SR 2010-11 (P.3/I.8) Point Wiring using Class A Materials a) Short point upto 3Mtr from tapping point to out let via switch etc complete as per specifications and directions of engineer in charge of the work.	Each	175.00	
41	4	b) Medium point above 3mtr upto 6mtr from tapping point to out let via switch		260.00	
42	3	C) Long point above 6mtrs upto 10mtrs from tapping point to outlet via switch		368.00	
43	2	Supplying and fixing superior quality modula switch mounting polyorbonate plate with ncessary supporting back plate with required nos. of machines screws, bolts nuts etc., complete on the existing metal/PVC box 1 to 3 Modular etc complete as per specifications and directions of engineer in charge of the work.	Each	82.00	
44	2	8 Modular		175.00	
45	15	Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plat 6Amps one way. etc complete as per specifications and directions of engineer in charge of the work.	Each	96.00	
46	6	6Amps 3way Socket.		165.00	
47	4	Stepped Fan Regulator		520.00	
48	6	Supply patty type fluorescent tube light fitting of 4' - 36/40 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking, locking type brass contact holder mounted on double fold type sheet base fully wired for used on 230 Volts A C Supply including fluourescent tube Group 'A' etc complete as per specifications and directions of engineer in charge of the work.		380.00	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
49	5	Supplying of Incandescent lamps C75B.C. 100Watts		14.00	
50	4	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system KPWD SR 2010-11 (P-23, I-23) Regulator Model (Khaitan, Crompton Geaves, Orient, Polar, Bajaj, Usha, Havells, Almonard 56" Sweep (1400 mm)	Each	1950.00	
51	1	Supplying and fixing 32Amps security and energy savings DP switch with key tag suitable to operate on 230 Volts 50Hz AC supply & completely wired on existing box KPWD SR 2010-11 (P.9/I.19) Group A	Each	630.00	
52	1	Supplying and fixing one of 230 volts PBBC bakelite straight or slant batten holder and wiring with in 60w/230 Volts lamps KPWD SR 2010-11 (P-13, I.2)	No	60.00	
53	1	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required 5-32 Amps SP KPWD SR 2010-11 (P.34/I.13)	Each	560.00	
54	1	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc KPWD SR 2010-11 (P.32/I.2) 20"x20"x2.5"		285.00	
55	1	Supplying and fixing of porcelain fuse channel with cut out on existing wooden /panel using necessary nuts, bolts and washers etc complete KPWD SR 2010-11 (P.30/I.3) 32 Amps etc complete as per specifications and directions of engineer in charge of the work.		100.00	
56	1	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipment on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit. The pit should be filled with equal proportion of salt and charcol 150mm alround the pipe to complete depth. The connection from the pipe to the conduit etc, is to be established through GI wire of size as per ISI specification 7.3.3 of Is 732 using 12mm dia nuts, washers and checknuts etc the pipe shall have 16 through holes of 122 mm dia etc complete as per specifications and directions of engineer in charge of the work.	No	1950.00	
57	10	INSULATED CABLE ON MESSENGER WIRE Using 2 single core wires for a single phas and 4 single core wires for 3 phase supplying and stringing PVC insulated and PVC sheathed 650/1100V class aluminium conductor of size supported by 3.15mm (10 SWG) GI messenger wire with two breaks insulators, one at each end of the span with suspenders at intervals of 0.75m. Each suspender shall be of porcelain reel insulator of suitable core through which insulated wire passes (single core or twin core as the case may be) and this reel insulator shall be fixed to the messenger wire using 2mm (No. 14SWG) GI wire suitably bent and twisted. Separate reel insulated shall be provided for each wire the messenger wire shall be bed-ended on the clamp provided to the departmental pole wide item No. 4 above c) 6 Sqmm etc complete as per specifications and directions of engineer in charge of the work.	Mtr	45.00	

Signature of the Contractor


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92